

SECTION 10343 CUPOLAS

PART 1 — GENERAL

1.01 DESCRIPTION

- A. Work includes: Furnish labor and materials to complete fabrication of ready-made cupolas as shown on Drawings. Work shall include but not be limited to:
 1. Wood curb (where required)
 2. Base section
 3. Middle section (louvers or windows)
 4. Roof section
 5. Weather vane
- B. Related Work Specified Elsewhere:
 1. Installation by carpenter trade
 2. Roofing material
 3. Flashing
 4. Sealants

1.02 SUBMITTALS

- A. Product Data:
 1. Manufacturer's published cut sheets showing model selections, colors, and weather vane selections
- B. Shop Drawings:
 1. Submit to Architect for approval showing connections of parts and anchorage system to roof structure.
 2. Show elevations that illustrate roof slope, louver placement, and weather vane.
- C. Samples:
 1. Submit cladding samples showing available textures and colors.
- D. Project Closeout Submittals:
 1. Submit Cupola Manufacturer's installation and maintenance instructions.

1.03 QUALITY ASSURANCE

- A. Manufacturer's Qualifications:
 1. Manufacturer shall have at least five (5) years' experience manufacturing cupolas equal to those specified in this section.

1.04 DELIVERY, HANDLING AND STORAGE

- A. Cupola Manufacturer shall package complete cupola including all parts, anchorage materials, and weather vane in wood crate of sufficient construction to protect cupola and all its parts.
- B. Contractor shall store cupola in covered area off the ground and protected from damage.

PART 2 — PRODUCTS

2.01 APPROVED MANUFACTURER

- A. New Concept Louvers
2940 South State Street
P.O. Box 583
Springville, Utah 84663
Phone: (801) 489-0614 or (800) 635-6448
E-mail: info@newconceptlouvers.com
www.newconceptlouvers.com

2.02 MANUFACTURED UNITS

- A. General:
 1. Three-part design for ease of installation
- B. Base Section:
 1. Wood construction with coated aluminum cladding
 2. Preinstalled 2" x 8" cleats to secure cupola to roof
- C. Louver Section:
 1. Wood framing with coated aluminum cladding
 2. Louvers: 0.019" thick coated aluminum stock with attached insect screen
 3. Screens: 9 x 9 ventmesh Fiberglas®
- D. Windows with Grids (special order)
- E. Roof section:
 1. 16-ounce copper cladding
 2. Options: Aluminum, flat sheet painted steel, shingles, or other as specified by Architect
- F. Weather Vane (optional):
 1. As selected by Architect from Cupola Manufacturer's complete list of weather vanes
- G. Models (choose one):
 1. Stansbury: Louvers, Square Base, Hip Roof
 2. Jamestown: Louvers, Square Base, Pagoda Roof
 3. Charleston: Louvers, Square Base, Bell Roof
 4. Estate: Louvers, Hexagon Base, Hip Roof
 5. Madison: Louvers, Hexagon Base, Pagoda Roof
 6. Richmond: Louvers, Hexagon Base, Bell Roof
 7. Georgetown: Louvers, Octagon Base, Hip Roof
 8. Providence: Louvers, Octagon Base, Pagoda Roof
 9. Bedford: Windows, Octagon Base, Bell Roof
 10. Windsor: Windows, Square Base, Hip Roof
 11. Trenton: Windows, Square Base, Pagoda Roof
 12. Vermont: Windows, Square Base, Bell Roof
 13. Nantucket: Windows, Hexagon Base, Hip Roof
 14. Davenport: Windows, Hexagon Base, Pagoda Roof
 15. York: Windows, Hexagon Base, Bell Roof
 16. Lexington: Windows, Octagon Base, Hip Roof
 17. Oxford: Windows, Octagon Base, Pagoda Roof
 18. Arlington: Windows, Octagon Base, Bell Roof

2.03 ACCESSORIES

- A. Attachments:
 1. Base Attachments: 4-inch-long bolts with washers and nuts supplied by Cupola Manufacturer
 2. Curbing Attachments (if required): 4-inch-long bolts with washers and nuts supplied by Cupola Manufacturer
 3. 2-inch-long painted stainless-steel replacement screws supplied by Cupola Manufacturer
- B. Cupola Curb (optional, for new construction):
 1. Wood construction, sized to fit cupola being installed
- C. Lights for windowed cupolas

Continued, next page ▶

2.04 FINISHES

- A. PVC-clad aluminum or baked enamel
- B. Color:
 - 1. As selected by Architect from manufacturers' standard 400 colors

PART 3 — EXECUTION

3.01 EXAMINATION

- A. Installation on Existing Roofing Material:
 - 1. Examine condition of roofing material and slope of roof to be certain cupola can be properly installed.
 - 2. Notify Architect in writing of unacceptable existing conditions.
- B. Installation on New Construction without Applied Roofing Material:
 - 1. Examine condition and size of opening to receive curb and cupola.
 - 2. Verify that roof slope, where applicable, is correct.
 - 3. Notify Architect in writing of unacceptable existing conditions.

3.02 PREPARATION

- A. Removal of Existing Shingles:
 - 1. Fiberglas®/asphalt shingles: Carefully remove ridge cap (row of shingles on peak of roof) where the cupola will be installed. (Other shingles may be left in place.)
 - 2. Shingles thicker than Fiberglas®/asphalt: Remove all shingles from area where cupola will be installed.
- B. Marking and Cutting Ventilation Hole (venting louvers only):
 - 1. Mark where hole in roof will be cut, coming in at least 1 inch from cleats that are installed in the base section (or 1 inch in from the cleats of the curb) and the same total distance in from the inside walls of sides that do not have cleats.
 - 2. Being careful not to cut through or into trusses or other structural lumber, cut out ventilation hole.

3.03 INSTALLATION

- A. Installation of Optional Curb (new construction):
 - 1. Using 4-inch bolts furnished by Cupola Manufacturer, install and attach cupola curb in accordance with Cupola Manufacturer's written installation instructions.
- B. Install cupola in accordance with Cupola Manufacturer's written installation instructions.
 - 1. Place base section in position and adjust so it is plumb and level. Use shims if necessary.
 - 2. Attach base section to roof.
 - a. If not using optional curb: Drill a 7/16-inch-diameter hole through each cleat (total of four holes) and into the roof. Bolt base to roof through the holes using bolts, washers, and nuts provided by Manufacturer with cupola.
 - b. If using optional curb (new construction): Attach cupola to curb in accordance with Cupola Manufacturer's written installation instructions, using the four 4-inch painted carriage bolts provided by Cupola Manufacturer.

- 3. Using specified sealant, seal around bottom of base section to keep water from leaking under cupola.
- 4. Place louver (or window) section on top of base section, with lip of base fitting snugly inside bottom of louver (or window) section.
- 5. Place roof section on top of louver (or window) section, with lip of roof section fitting snugly inside top of louver (or window) section.
- 6. Replace painted 1/2-inch screws at corners of louver (or window) section with 2-inch painted stainless-steel screws included with cupola.
 - a. Replace screws one at a time, and finish replacing each screw before removing next screw.
 - b. After removing existing 1/2-inch screw, predrill 7/64-inch-diameter hole for 2-inch replacement screw.
 - c. To avoid indenting aluminum, do not "bottom out" replacement screw. Finish tightening by hand.

3.04 CLEANING

- A. Remove leftover materials from installation caused by work of this section from site and dispose of legally.
- B. Clean cupola to be free of dirt or smudging caused by storage, handling, or installation of cupola.

END OF SECTION